

**ROAD RENOVATION/RECONSTRUCTION, CONSTRUCTION, & MAINTENANCE**

See Also Exhibit A (Sheets 1-4) and Exhibit C

Unit #	Length (ft)	Surface		Stations	Description	Type	Total Stations	Total Length	
		Width (ft)						(ft)	Distance (mi)
4-1	3,064.53			30.65		Dedicated Skid Road	30.65	3,064.53	0.58
	7,763.22			77.63	Wolfe Camp Rd	Haul Route	77.63	7,763.22	1.47
	663.60			6.64	ROW WAOR-65294	Road Maintenance	6.64	663.60	0.13
	460.19			4.60	Echo Bay Rd Use Agreement	Road Maintenance	4.60	460.19	0.09
	1,791.60	12		17.92		Temp Road Construction	17.92	1,791.60	0.34
	1,000.00	12		10.00	5 Skid Rds & Temp Rd Segments	Decommission First 200'	10.00	1,000.00	0.19
6-1	1,499.53			15.00	Forwarder Routes	Dedicated Skid Road	15.00	1,499.53	0.28
	10,397.29			103.97	Day Creek Rd	Haul Route	103.97	10,397.29	1.97
	2,423.99			24.24	\$155.00 Rd Easement Log Transport Cost	Road Maintenance	24.24	2,423.99	0.46
	17,609.52			176.10					
	2,943.22			29.43	Access Rd Easement	Road Reconstruction	208.00	20,799.68	3.94
	246.94			2.47	BLM connecting to 751 Rd				
	841.19	12		8.41	Optional Spur Rd	Temp Road Construction - Decommission All New Rds	10.86	1,086.40	0.21
	245.21	12		2.45	Optional Spur Rd				
	2,830.22			28.30	751 Rd; Pre/During/Post Haul Maintenance	USFS Road Maintenance	89.01	8,900.50	1.69
	6,070.28			60.70	750 Rd; Pre/During/Post Haul Maintenance				
4,842.61			48.43	751 Rd; Pre/During/Post Haul Maintenance	USFS Road Reconstruction	48.43	4,842.61	0.92	
9-2	5,551.00			55.51	Lone Ranch Creek Rd	Haul Route	75.14	7,513.82	1.42
	1,962.82			19.63	Day Creek Rd				
	561.00			5.61		Road Reconstruction	5.61	561.00	0.11
	2,690.03			26.90		Road Maintenance	26.90	2,690.03	0.51
	400.00	12		4.00	2 Rd Segments	Decommission First 200'	4.00	400.00	0.08
	511.17	12		5.11	Lower Spur	Temp Road Construction	9.12	912.31	0.17
401.14	12		4.01	Upper Spur					
6,276.34	14		62.76	DNR Rd Agreement	DNR Road Renovation	78.96	7,895.56	1.50	
1,619.22	14		16.19	DNR Rd Agreement					

15-1	1,138.23		11.38 DNR Rd Agreement	Dedicated Skid Road	11.38	1,138.23	0.22
	3,060.48		30.60 Day Creek Rd				
	1,968.50		19.68 Day Creek Rd	Haul Route	69.79	6,978.51	1.32
	1,949.54		19.50 Day Creek Rd				
	1,977.72		19.78 O'Halloran Rd Use Agreement				
	2,005.62		20.06 BLM Northern Piece	Road Reconstruction	46.26	4,626.33	0.88
	386.00		3.86 BLM Southern Piece				
	257.00		2.57 BLM Southern Piece				
	795.49	12	7.95 BLM Southern Piece	Road Reconstruction	7.95	795.49	0.15
	200.00	12	2.00 1 Rd Segment	Decommission First 200'	2.00	200.00	0.04
2,589.38	12	25.89 BLM	Temp Road Construction	25.89	2,589.38	0.49	
16-1	4,609.12	14	46.09 DNR Rd Agreement: Ops p.11	DNR Road Renovation	46.09	4,609.12	0.87
	1,848.99	12	18.49 O'Halloran Rd Use Agreement	Road Reconstruction	18.49	1,848.99	0.35
	617.00	12	6.17 BLM	Road Reconstruction	6.17	617.00	0.12
21-1	1,906.67		19.07 Schostak Access Agreement	Dedicated Haul Road	19.07	1,906.67	0.36
	3,943.71		39.44 Hurlburt Rd				
	234.04		2.34 O'Halloran Rd Use Agreement	Haul Route	41.78	4,177.75	0.79
	3,422.43		34.22 Durkos Ln Access Agreement	Road Reconstruction	47.33	4,733.12	0.90
	1,310.69		13.11 Durkos Access Agreement				
	400.00	12	4.00 2 Rd Segments	Decommission First 200'	4.00	400.00	0.08
	2,186.68	12	21.87				
	132.98	12	1.33 O'Halloran Rd Use Agreement	Temp Road Construction	24.30	2,430.39	0.46
110.74	12	1.11 Durkos Access Agreement					
				<b>Dedicated Skid Road</b>	76.09	7,608.96	1.44
				<b>DNR Road Renovation (Reconstruction)</b>	125.05	12,504.68	2.37
				<b>Haul Route</b>	368.31	36,830.59	6.98
				<b>Road Maintenance</b>	122.53	12,252.95	2.32
				<b>Road Reconstruction</b>	339.82	33,981.61	6.44
				<b>Temp Road Construction</b>	88.10	8,810.08	1.67
				<b>USFS Road Maintenance</b>	89.01	8,900.50	1.69
				<b>USFS Road Reconstruction</b>	48.43	4,842.61	0.92
				<b>Road Decommissioning</b>	30.86	3,086.40	0.58

Decommissioning Constructed Landings & Skid Trails (Total AC):

12.94


**Road Renovation:** The contract will require the purchaser to renovate approximately 4.31 miles of existing roads and trails. However, most road renovation can be accomplished during normal logging operations. Most of the road renovation could be accomplished by simple brushing and removal of small trees that have grown into existing roads.

**Road Construction:** The location and length of temporary roads, including skid roads may be adjusted at the time of contract implementation. All temporary roads on BLM land must be decommissioned. See also attached Spec Sheets.

**Road Maintenance:** See Exhibit C

**Decommissioning:** Decompact temporary road construction surfaces, skid trails, and constructed landings. Rip to an approximate 10-18" depth, and place woody debris on deconstructed surfaces.

### Specification Sheet



1. <u>Road Standard</u>	<u>SN-14</u>	_____	_____
2. <u>Alignment</u>			
Max. degree of curve	<u>75°</u>	_____	_____
3. <u>Road Width</u>			
Subgrade	<u>14 ft.</u>	_____ ft.	_____ ft.
Subgrade at turnout	<u>24 ft.</u>	_____ ft.	_____ ft.
4. <u>Gradient</u>			
Max. favorable	<u>15%</u>	_____	_____
Max. adverse	<u>15%</u>	_____	_____
5. <u>Clearing Width</u>			
Beyond top of cut	<u>3 ft.</u>	_____ ft.	_____ ft.
Beyond toe of fill	<u>0 ft.</u>	_____ ft.	_____ ft.
6. <u>Surfacing</u>			
Min. width	<u>12 ft.</u>	_____ ft.	_____ ft.
Compacted depth	<u>4 in.</u>	_____ in.	_____ in.

7. Full Bench Construction

Slopes 60% and over shall be full bench construction.

8. Excavation Slopes

Common

Soft rock and shale

Solid rock

Cut Slopes

1:1

3/4:1

1/2:1

Fill Slopes

1 1/2:1

Angle of repose

9. Extra Subgrade Widths

Add to each fill shoulder 1 ft. for fills 1-6 ft., 2 ft. for fills over 6 ft.

Widen inside shoulder of all curves as follows:

When degree of curve equals:

7° - 21° -- 1 ft.      49° - 64° -- 4 ft.

22° - 35° -- 2 ft.      65° - 115° -- 5 ft.

36° - 48° -- 3 ft.

10. Turnouts


Standard length: 50 ft., approach length: 25 ft.

Width: 10 ft. in addition to subgrade width.

Location: intervisible or not over 700 ft. apart.


Surfacing width: 10 ft. in addition to min. surface widths.

Typical Turnout



## Water Dip Specifications


(For Roads with Grades Greater Than 8 Percent)




WATER DIP SPECIFICATIONS

ROAD GRADE IN %	SOIL TYPE		ROAD GRADE IN %	SOIL TYPE	
	GRANITIC OR SANDY	SHALE OR GRAVEL		GRANITIC OR SANDY	SHALE OR GRAVEL
1	1000	1000	9	300	900
2	900	1000	10	300	800
3	600	1000	11	300	700
4	400	1000	12	300	700
5	400	1000	13	300	600
6	300	1000	14	300	600
7	300	1000	15	300	500
8	300	900			


# EXHIBIT \_\_\_\_\_




**LOG BARRICADE**




1. Log barricade shall be constructed as shown above.
2. Exact location is listed in Work List.
3. All barricades shall be skewed 30 degrees.
4. The length shall be sufficient to extend from the cut bank to the fill slope.
5. The minimum small end diameter of the log barricade shall be 24".




**TRENCH BARRICADE**



1. Barricade length shall extend across the entire road surface to a point sufficient to prohibit motor vehicle traffic.
2. Exact location is listed in the Work List.
3. All barricades shall be skewed as needed to drain or as directed by the Authorized Officer.




**WATER BAR**



1. Water bars shall be constructed as shown above.
2. Exact location will be flagged by the Authorized Officer prior to construction.
3. All water bars shall be skewed 30 degrees.
4. Upon completion of skidding logs, for the logging season, each skid road will have cross drainage constructed as shown above.

**SKEW DIAGRAM**



**WATER BAR SPACING\* BY EROSION CLASS^**

ROAD GRADE	HIGH	MODERATE	LOW
%	FEET	FEET	FEET
2-5	200	300	400
6-10	150	200	300
11-15	100	150	200
16-20	75	100	150
21-35	50	75	100
35+	50	50	50

\* Spacing is determined by slope distance and is the maximum allowed for the grade.





^ The erosion classes include the following rock types:  
**High:** Granite, sandstone, andesite porphyry, glacial or alluvial deposits, soft matrix conglomerate, volcanic ash, and pyroclastics.  
**Moderate:** Basalt, andesite, quartzite, hard matrix conglomerate, and rhyolite.  
**Low:** Metasediments, metavolcanics, and hard shale.

*ALWAYS  
 THINK  
 SAFETY*




REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>STANDARD                      BARRICADE AND                      WATER BAR DETAILS</b>			
DRAFTED BY: BLM		SCALE: NONE	
DATE: JULY 2019		SHEET: 1 OF 1	
DRAWING NO.: OR-11-0113.4-4			

# EXHIBIT \_\_\_\_\_


## CULVERT INSTALLATION TYPES



## CATCH BASIN



## SKREW DIAGRAM



THE GRADE OF CROSSEDRAINS SHALL BE AT LEAST 2% GREATER THAN THE GRADE OF THE DITCH.

**ALWAYS  
THINK  
SAFETY**

REV. NO.	DESCRIPTION	DATE	APPROV.
UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT MEDFORD DISTRICT - MEDFORD, OREGON			
<b>TYPICAL CULVERT INSTALLATION DETAILS</b>			
DRAFTED BY: BLM		SCALE: NONE	
DATE: JULY 2019		SHEET: 1 OF 2	
DRAWING NO.: OR-11-9113,4-4			